

# Real Time Experience Studying ADOT I-10 Dust Project Implementation

2020 Arizona Dust Workshop, March 3, 2020

# Project Overview (who was involved)

- Designers
  - Kimley-Horn
  - WSP
- Contractors
  - Coffman Specialties
  - Sturgeon Electric
- Equipment
  - Enterprise Electronics Corporation (EEC)
  - Vaisala
- DPS
- National Weather Service
- ADOT
  - TOC, TSMO, IDO, Communications and South Central District
- FHWA



# Project Details

- Project award to Coffman Specialties in November of 2017, bid of \$58,465,000
- 780,000 yrd<sup>3</sup> roadway ex.
- 930,000 yrd<sup>3</sup> of borrow
- 211,000 yrd<sup>2</sup> of PCCP
- 120,000 tons of asphalt
- Civil work completed in Oct.'19



October 2011 – Three dust related crashes  
near Picacho / Casa Grande.

- 24 vehicles
- 16 injured
- 1 dead


October 2013 –  
dust storm related  
crash on I-10

- 19 vehicles / 7 Trucks
- 12 injured
- 3 dead



# Project Goals

- Provide early warning of blowing dust approaching and within the corridor
- Measure visibility within the corridor
- Provide video to allow the ADOT TOC to have ‘eyes on the road’
- Disseminate real-time information to motorists
- Implement lowered speed limits within corridor



## X-BAND RADAR (RANGE-X5)

## CLOSED CIRCUIT TV (5)

## SPOT DETECTOR (13)

## DYNAMIC MESSAGE SIGN (4)

## VARIABLE SPEED LIMIT SIGN (16)

## SPEED FEEDBACK SIGNS (2)

**Vaisala Equipment:**

- PWD 10 (measure visibility) (13)
- RG13H (rain gauge)(1)
- WXT536 (wind, temp. and humidity)(3)



```
<name>AWS_3</name>
</target>
<value code="TA">73.0</value>
<value code="RH">43</value>
<value code="TD">49.4</value>
<value code="PA">24.8</value>
<value code="WS">0.2</value>
<value code="WD">150</value>
<value code="WS2">0.2</value>
<value code="WD2">158</value>
<value code="WS10">/</value>
<value code="WD10">/</value>
<value code="PR1">0.000</value>
<value code="PR3">0.000</value>
<value code="PR6">0.000</value>
<value code="PR12">/</value>
<value code="PR24">/</value>
<value code="RI">0.000</value>
<value code="VIS1_1">6561</value>
<value code="VIS10_1">6561</value>
```



**AWS310 (the brains)**  
Each of the three locations talks to all 13 visibility sensors

codespace	shortname	Parameter Name	group	qualifier	period (seconds)	min length	max length	unit	low	high	missing
AZDUST	PWDS_8	PWD Status (Sensor 8)	Technical	Instant	60	0	2	Code	0	99	///
AZDUST	VIS1_9	Visibility 1 Minute Average (Sensor 9)	Atmospheric	Average	60	0	5	feet	0	99999	///
AZDUST	VIS10_9	Visibility 10 Minute Average (Sensor 9)	Atmospheric	Average	600	0	5	feet	0	99999	///
AZDUST	PWDS_9	PWD Status (Sensor 9)	Technical	Instant	60	0	2	Code	0	99	///
AZDUST	VIS1_10	Visibility 1 Minute Average (Sensor 10)	Atmospheric	Average	60	0	5	feet	0	99999	///
AZDUST	VIS10_10	Visibility 10 Minute Average (Sensor 10)	Atmospheric	Average	600	0	5	feet	0	99999	///
AZDUST	PWDS_10	PWD Status (Sensor 10)	Technical	Instant	60	0	2	Code	0	99	///
AZDUST	VIS1_11	Visibility 1 Minute Average (Sensor 11)	Atmospheric	Average	60	0	5	feet	0	99999	///
AZDUST	VIS10_11	Visibility 10 Minute Average (Sensor 11)	Atmospheric	Average	600	0	5	feet	0	99999	///
AZDUST	PWDS_11	PWD Status (Sensor 11)	Technical	Instant	60	0	2	Code	0	99	///
AZDUST	VIS1_12	Visibility 1 Minute Average (Sensor 12)	Atmospheric	Average	60	0	5	feet	0	99999	///
AZDUST	VIS10_12	Visibility 10 Minute Average (Sensor 12)	Atmospheric	Average	600	0	5	feet	0	99999	///
AZDUST	PWDS_12	PWD Status (Sensor 12)	Technical	Instant	60	0	2	Code	0	99	///
AZDUST	VIS1_13	Visibility 1 Minute Average (Sensor 13)	Atmospheric	Average	60	0	5	feet	0	99999	///
AZDUST	VIS10_13	Visibility 10 Minute Average (Sensor 13)	Atmospheric	Average	600	0	5	feet	0	99999	///
AZDUST	PWDS_13	PWD Status (Sensor 13)	Technical	Instant	60	0	2	Code	0	99	///
AZDUST	BT	Battery Voltage	Technical	Instant	60	0	4	Vdc	0	99	///
AZDUST	EXTDC	Supply Voltage	Technical	Instant	60	0	4	Vdc	0	99	///
AZDUST	STATUS	QML Status Code	Technical	Instant	60	0	2	Code	0	99	///
AZDUST	WXTS	WXT Status Code	Technical	Instant	60	0	2	Code	0	99	///

```
<name>AWS_3</name>
</target>
<value code="TA">73.0</value>
<value code="RH">43</value>
<value code="TD">49.4</value>
<value code="PA">24.8</value>
<value code="WS">0.2</value>
<value code="WD">150</value>
<value code="WS2">0.2</value>
<value code="WD2">158</value>
<value code="WS10">/</value>
<value code="WD10">/</value>
<value code="PR1">0.000</value>
<value code="PR3">0.000</value>
<value code="PR6">0.000</value>
<value code="PR12">/</value>
<value code="PR24">/</value>
<value code="RI">0.000</value>
<value code="VIS1_1">6561</value>
<value code="VIS10_1">6561</value>
```



**AWS310 (the Brains)**  
Each of the three locations talks to all 13 visibility sensors



Integration Team:  
Kimley-Horn, Flir & ADOT

Testing through June and  
activation by first of July







# Pull Aside – Stay Alive

# Questions?

Kevin Duby  
[kduby@azdot.gov](mailto:kduby@azdot.gov)

602-712-7012

David Locher  
[dlocher@azdot.gov](mailto:dlocher@azdot.gov)

602-712-2317